

PRE-INSTALLATION INSTRUCTIONS AND SITE PREPARATION



This form must be signed and returned with your order

STEEL WATER TANKS from 27,000L - 375,000L

PREPARING SAND PAD:

1. Prepare a sand pad 2 metres larger in diameter than the chosen tank (4 metres larger for HGT375 and all three-ring tanks). The pad must be 150mm deep, and free of vegetation.
Tree roots, etc, must be totally removed with no possibility of growing back.
Ensure sub soil has adequate compaction (minimum 50kpa).
2. The preferred base material is free draining sand, level over the entire area (with no more than a +/-10mm variation) It should also be free of any sharp objects, clay lumps, stones etc. Must be good quality clean sand. Crusher dust is also acceptable at an aggregate size of 5mm or less
3. Important; the sand pad must be level - please double check.
4. If the site is cut and filled to form the base for the tank, ensure there is adequate compaction (minimum allowable bearing pressure of 50kPa) of the sub soil to avoid subsidence. Adequate drainage must be installed to divert water run off away from the tank. Please see back of page for tank sizes, sand volumes and diagrams.
5. Pad preparation must be up to these standards, if not and it is necessary for our installers to leave the site and reschedule a new installation date this will incur a charge for travel, accommodation (if required) and wages, which will be charged to you by the installers.

ON THE DAY OF INSTALLATION:

1. 100mm of water must be supplied by the purchaser to be placed in the tank (350mm for 3 ring tanks). This must happen on the day of installation to secure the liner and stop it from any future movement (If no water is supplied this will void your warranty). In high wind areas 200mm of water is required (500mm for 3 ring tanks), please see back of page for volumes of water needed per tank.
2. If prior arrangement of the placement of the fittings has not been made then someone will need to be on site to explain where the fittings need to be placed on the tank on the day of installation.
3. Full payment must be made **before installation**.

AFTER INSTALLATION IS COMPLETE:

1. 75mm thick x 400mm of Blue Metal or Crushed Rock (3/4" or 20mm) must be placed around the total circumference of the base of the tank and maintained for the life tank at the stated depth and width. This is designed to stop erosion from water run off or strong winds. (If no Blue Metal is placed around the tank this will void your warranty). Please see back of page for volumes of blue metal/crushed rock needed. Site must be kept vegetation free.
2. Inspection hatches must be locked (Lock to be supplied by purchaser). Unauthorized entry into the tank is prohibited.

CLIENT RESPONSIBILITIES

ACCESS INTO THE SITE:

Please ensure clear access for vehicles to site.
Most installers will need access for a ute with a trailer or a small truck. (If the roof sheets are to be sent to site there may be a large truck or semi needing access. Please advise the installer).

Please stipulate if 4WD is necessary to access the site.

SUFFICIENT FALL FROM GUTTERS:

It is the purchaser's responsibility to make sure there is sufficient fall from the Gutters of premises to the tank. (Tank wall height CT Range 2.27m, HGT range 2.31m, HGT375 3.45m). Note: All three-ring tanks are 3.45m.

CHECK WITH LOCAL SHIRE / COUNCIL:

It is the purchasers responsibility to check with local Shire / Councils with regards to building licenses, building envelopes and any bylaws.

PURCHASERS RESPONSIBILITY:

It is the purchaser's responsibility that all the conditions are met and work is completed on the pad before the installation date.

CANCELLATION POLICY:

Cancellation may result in the forfeit of all or part of your deposit.

PAYMENT OF ACCOUNTS

Full payment of accounts must be made on time.
Overdue accounts will be subject to interest at the rate of 8% p.a, calculated for the period the account is due until the date it is paid.

In the event that an overdue account is referred to a collection agency and/or law firm, Heritage Tanks may recover from the Purchaser all fees, costs and expenses in full, including legal demand costs, incurred by Heritage Tanks in recovery of the outstanding monies.

Heritage Tanks retains ownership of all goods until paid in full.

SUITABLE DATE:

Once your sand pad is completed to the standards specified above, contact your State Distributor to arrange a suitable installation date as agreed to by both parties.

WARRANTY:

After the completion of a signed order form, the compliance of the above conditions and the full payment, your 20 year pro rata warranty will be validated.

Failure of any of the above will void your warranty.

WIND RATING:

These installation instructions are based on a Category A wind rating. If your tank is in a Category B or C wind rating (eg. Northern Queensland coast line is rated Category B & C) you must have a minimum of 30% capacity of water in the tank under adverse wind conditions.

I/We the undersigned have read, understand and will abide by the guidelines outlined in this form.

Name / Position:

Date:

Signature:

Name / Position:

Date:

Signature:
